

**Govt. of West Bengal**  
**Irrigation & Waterways Dte.**  
**Office of the Executive Engineer**  
**West Midnapore Division**  
**Medinipur, Paschim Medinipur**  
 email id- [eeamid2012@gmail.com](mailto:eeamid2012@gmail.com)

**NIT NO:-WBIW/EE/WMD/NIT 05 of 2016-17****Sl. No. 03**


Schedule of Quantity, Unit, Rate and Amount for the work, "Periodical maintenance of JHILLI MAIN & DISTRIBUTORY Canal for Khariff Irrigation 2016 during the month July to October under Gopiballavpur Irrigation Section of Jhargram Irrigation Sub-Division within West Midnapore Division.

**Amount put to Tender : ₹ 206,163.00****Earnest Money : ₹ 4,123.00****Time allowed for Completion : 120 days**

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in charge.	5116.00	Sqm	₹ 7.70	Rupees seven and paise seventy only	₹ 39,393.00
2	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge.	1084.00	Cum	₹ 76.70	Rupees seventy six and paise seventy only	₹ 83,143.00
3	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	540.00	M	₹ 23.60	Rupees twenty three and paise sixty only	₹ 12,744.00
4	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	270.00	M	₹ 6.30	Rupees six and paise thirty only	₹ 1,701.00
5	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	M	₹ 19.30	Rupees nineteen and paise thirty only	₹ 3,860.00
6	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2000.00	each	₹ 5.00	Rupees five and paise zero only	₹ 10,000.00
7	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should	2000	each	6.30	Rupees six and paise thirty only	₹ 12,600.00
8	Supply of Labour (Mazdoor)	40	Day	₹ 206.00	Rupees two hundred six only	₹ 8,240.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
9	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (g) Moorum	57	Cum	540.00	Rupees five hundred forty only	₹ 30,780.00
10	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) <i>Correction factor 0.75</i>	43	Cum	₹ 86.10	Rupees eighty six and paise ten only	₹ 3,702.00
Total Amount put to Tender in figure =						₹ 206,163.00
Total Amount put to Tender in word :						Rupees two lakh six thousand one hundred and sixty three only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)