



सत्यमेव जयते

GOVT. OF WEST BENGAL
OFFICE OF THE EXECUTIVE ENGINEER
COOCH BEHAR IRRIGATION DIVISION
DEBI BARI, COOCH BEHAR.
Tel & Fax: (03582) 228305

Memo. No- 1138

Dated - 5.7.16

N.I.Q.No- 02(m) of 2016-17 of Executive Engineer, CoochBehar Irrigation Division

Sealed quotation in plain paper are hereby invited by the undersigned for the following work from the eligible Bonafide outsiders having credential of execution of similar nature of works which will be received up to 3.00 P.M. on 14/07/2016 and the same will be opened at 3.30 P.M. on same day in presence of the participating agencies who will present at the time.

Name of the work- M/R to Coochbehar T.P. embankment along the L/B of river Torsa in P.S. Kotwali, Dist. Coochbehar (Development of Garden including preparation of land and proper plantation in front of sech Niwas at Debibari complex under Coochbehar Irrigation Division).

Sl. No	Description of item	Qty	Unit	Rate including all taxes (If any)	Amount including all taxes (If any)
1	Trenching in ordinary soil up to a depth of 45 cm. including removal and stacking of serviceable materials and then disposing of by spreading and neatly leveling within a lead of 50m. and making up the trenched area to proper level by filling with earth or earth mixed with manure before and after flooding trench with water (excluding cost of imported earth or manure) in all respect as per direction of the Engineer-in-charge.	626 Cum	Cum		
2	Flooding the trenched ground with water including making kiaries and dismantling the same in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Sqm		
3	Clearing Grass and removed of the rubbish up to a distance of 50 m outside the periphery of the area cleared in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Sqm		
4	Uprooting weeds from the trenched area after 10 to 15 days of flooding with water including disposal of uprooted vegetation in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Sqm		
5	Removal of rubbish/ stones, brick-bats etc. from the site with carriage charges, loading and unloading in all respect as per direction of the Engineer-in-charge.	94 Cum	Cum		
6	Rough dressing the trenched ground including breaking clods in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Cum		
7	Supply and stacking of good earth at site including royalty, carriage, loading-unloading with all leads and lifts(the earth measured in stacks will be reduced by 20% for payment) in all respect as per direction of the Engineer-in-charge.	94 Cum	Cum		
8	Supplying of dung manure for trenched area at site including royalty carriage loading-unloading with all leads and lifts (the dung manure measured in stacks will be reduced by 8% for payment) in all respect as per direction of the Engineer-in-charge.	94 Cum	Cum		
9	Spreading of good earth & dung manure in required thickness (cost of good earth to be paid separately) in all respect as per direction of the Engineer-in-charge.	105 Cum	Cum		
10	Mixing of good earth & dung manure in required proportion for lawn in all respect as per direction of the Engineer-in-charge.	105 Cum	Cum		
11	Fine dressing the ground in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Sqm		

Contd. to page-2

Sl. No	Description of item	Qty	Unit	Rate including all taxes (If any)	Amount including all taxes (If any)
12	Supplying and stacking of good quality local Doob grass as per prevailing local market rate in all respect as per direction of the Engineer-in-charge.	139 Sqm	Sqm		
13	Grassing with Doob grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying goods earth if needed (the good earth shall be paid for separately) (in rows 7.5cm. apart in either direction) in all respect as per direction of the Engineer-in-charge.	1392 Sqm	% Sqm		
14	Preparation of beds for hedging by excavating 60cm deep and trenching the excavated base to a further depth of 30cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of staked volume of manure after reduction by 8%) flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc, including staking and disposal of material declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50m, lift up to 1.5m complete.(cost of manure or extra earth to be paid for separately) in all respect as per direction of the Engineer-in-charge.	24 Cum	Cum		
15	Supplying of disease free healthy plant material at site including carriage, loading-unloading charges in all respect as per direction of the Engineer-in-charge.	534 Nos	Each		

Quotation must be submitted with self attested Xerox copy of PAN, Professional Tax, Trade license, VAT registration certificate, Experience certificate etc. Time of completion of work is 90(Ninety) days.

The intending quotationers will have to quote their rates both in figure & word for the specified item of work in accordance with the specification, terms & conditions given above. The acceptance of the quotation will rest upon the competency of the Superintending Engineer, North East Irrigation Circle-I. Club Road, Jalpaiguri.

The Lowest quotationer will have to deposit a bank draft amounting to 2% (Two percent) of the total quotation value drawn in favour of the "Executive Engineer, Cooch Behar Irrigation Division" drawn from any nationalized bank .

The lowest quotationer whose quotation is accepted will have to execute an agreement in triplicate with the undersigned in W.B. Form No-2911(i)/(ii) of the accepting the terms and conditions.

Sgt 5.6.16
Executive Engineer

Cooch Behar Irrigation Division
Cooch Behar

Memo. No- *1138/1(10)*
Copy forwarded to the:-

Dated - *5.7.16*.

- 1) Superintending Engineer , North East Irrigation circle –I, Club Road, Jalpaiguri (in duplicate).
- 2) Executive Engineer, Cooch Behar Division Social Sector, P.W. Dte., Cooch Behar.
- 3-6) Sub-Divisional Officer, Tufanganj /CoochBehar /Mathabhanga Irrigation Irrigation Sub-Division and Coochbehar Investigation Sub-Division No-I.
- 7-8) Sr. Divisional Accountants Officer/ Estimator
- 9) Office Notice Board.
- 10) Secretary, Contractors' Association, Cooch Behar.

Sd/-S.K. Saha

Executive Engineer
Cooch Behar Irrigation Division
Cooch Behar