NIT NO. WBIW/EE/KCD-I/NIT 04 OF 2016-17

SL. No. 05

Schedule for the work: "M/R to Minor-E in between Ch.10.00 and Ch.82.00 of Dy No.3 of K.M.C.(L) under Dubrajpur Section of K.C. Sub-Divin. No.IV, Sarenga, under K.C. Divin. No.I, Amlagora, during 2016-17".

| SI. No. | Description of Item | Quantity | Unit | Rate (Rs.) | Unit | Amount (Rs.) |
|------------|---|----------|------|------------|------|--------------|
| | Earthwork in excavation in the canals / drainage channels / borrowpits / River bed / slope of bank as noted below as per designed section & throwing the spoils in layer of 23 cm. for making banks as per profile or to deposit the same in any other place as wanted by the Engineer-in-Charge within an initial lead of 30 metre and initial lift of 2.00 metre including breaking clods, rough dressing etc. complete as per direction of the Engineer-in-Charge. (Including dewatering as necessary) a) Local soil / soil mixed with moorum or kankar / silt, dry or moist / slushy silt / sticky soil. | | | (1.10.1) | | (NS.) |
| 2 (| Cutting and remaining the | 637.33 | Cum. | 77.00 | Cum | 49074.00 |
| t c | Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-Charge. | 1316.74 | Cana | 10.00 | | |
| | | 1310.74 | Sqm. | 10.00 | Sqm. | 13167.00 |

(Rupees sixty two thousand two hundred and forty one only)

Executive Engineer

K.C. Division No. 1

Amlagora , Paschim Medinipur

Signature of the Contractor(s)