## Page 1 of 1

Govt. of West Bengal Irrigation & Waterways Dte. Office of the Executive Engineer West Midnapore Division Medinipur, Paschim Medinipur

## WBIW/EE/WMD/NIT 19 of 2016-17

SI. No. 2

Schedule of Quantity, Unit, Rate and Amount for the work :- "Emergent strengthening and widening of Chetua Circuit Embankment from Ch. 40.00 Km to 40.47 Km (working length = 470.00 meter) along R/B of River Palaspai at Mouza Ajuria in G. P. Palaspal, Block- Daspur- II, Dist. Paschim Medinipur under Ajuria Section of Ghatal Irrigation Sub- Division within West Midnapore Division."

Amount put to Tender :

₹ 4,80,912.00

Earnest Money :

₹ 9,618.00

Time allowed for Completion :

SI.		No. or Quantity	Unit	Estimated Rate		Amount
No.				Figure	Word	Autount
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-incharge.	2829.40	sqm	₹ 7.70	Rupons seven and paise seventy only	₹ 21,786.00
	Earthwork, transporting the earth by manually operated thela/ van/ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	2546.46	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 3,53,703.00
- 5	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. 2 (two) extra.	2546.46	cum	₹ 41,40	Rupees forty one and paise forty only	₹ 1,05,423.00
	Total Amount put to Tender in figure =					₹ 4,80,912.00
	Total Amount put to Tender in word :	Rupees four lakhs eighty thousand nine hundred				

Executive Engineer West Midnapore Division Irrigation & Waterways Dte. Paschim Medinipur

I / We do hereby agree to do the above work @	
Above / Less / At par than this Schedule Of Rates attached herewith.	
<del>(a</del>	(Signature of the Contractor)