

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

WBIW/EE/WMD/NIT 19 of 2016-17

Sl. No. 6

Schedule of Quantity, Unit, Rate and Amount for the work :- "Emergent strengthening of Dussaspur Circuit Embankment in between Ch. 1.00 Km & Ch. 1.35 Km over R/B of River Old cossye in Mouza- Poshtanka in G. P. Sarberia- II, Block- Daspur-I, Dist. Paschim Medinipur under Dussaspur - II Section of Ghatal Irrigation Sub- Division under West Midnapore Division."

Amount put to Tender : ₹ 3,90,801.00

Earnest Money : ₹ 7,816.00

Time allowed for Completion :

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Earthwork, transporting the earth by manually operated thela/ van/ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	2167.50	cum	₹ 138.90	Rupees one hundred thirty eight and paise ninety only	₹ 3,01,066.00
2	Extra rate in Item no. 1 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. 2 (two) extra.	2167.50	cum	₹ 41.40	Rupees forty one and paise forty only	₹ 89,735.00
Total Amount put to Tender in figure =						₹ 3,90,801.00
Total Amount put to Tender in word :						Rupees three lakh ninety thousand eight hundred and one only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....  
Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)