## Page 1 of 2

Govt. of West Bengal Irrigation & Waterways Dte. Office of the Executive Engineer West Midnapore Division Medinipur, Paschim Medinipur

## WBIW/EE/WMD/NIT 19 of 2016-17

Sl. No. 17

Schedule of Quantity, Unit, Rate and Amount for the work: "Emergent repairs to inspection path in between Ch-11.00 Km. & 12.40 Km. (working length 1400 mtr.) of TE1H1 embktt., R/B of River Cossye under West Midnapore Division."

Amount put to Tender:

₹ 4,81,353.00

Earnest Money :

₹ 9,627.00

Time allowed for Completion:

SI.		No. or Quantity	Unit	Estimated Rate		Amount
No.				Figure	Word	Announc
1	Dressing, levelling including mending damages of the rain cuts and pot holes (not exceeding 30 cm depth) to the embankment including nominal earthwork for cutting or filling etc. as per direction of the Engineer-in-charge	2800.00	Curn	₹ 7.70	Rupees Seven and Paise Seven zero Only	₹ 21,560.00
2	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge, (g) Moorum.	420.00	Cum	₹ 540.00	Rupees five hundred forty and Paise zero Only	₹ 2,26,800.00
	© Brick bat (1st class)	63.00	Cum	₹ 1,160.00	Rupees one thousand one hundred sixty and Paise zero	₹ 73,080.00
3	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials  (a) For a distance above 20 km and up to 50 km (per km) = 30 km. extra lead.	420.00	Cum	₹ 285.00	Rupees Two hunderd eighty five and Paise zero Only	₹ 1,19,700.00
- 1	(b) For a distance above 50km upto 100km(per/km) Total distance 52Km 2 (two) extra lead	450.00	Cum	₹ 16.80	Rupees two hunderd eighty five and Paise zero Only	₹ 7,560.00
	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requsite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge, (measurement to be made on finished work) Compaction factor 0.67.	42.00	Cum	₹ 131.70	Rupees one hundred thirty one and Paise seven zero Only	₹ 5,531.00

## Page 2 of 2

SI.	Description of Items  Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work)  Compaction factor 0.75	No. or 315.00	Unit Cum	Estimated Rate		Amount
5				₹ 86.10	Ropees eighty six and Paise one zero Only	₹ 27,122.00
_	Total Amount put to Tender in figure =					₹ 4,81,353.00
	Total Amount put to Tender in word :	Rupees Four Lakh eighty one Thousand three hundred & fifty three & paise zero Only				

Executive Engineer
West Midnapore Division
Irrigation & Waterways Dtc.
Paschim Medinipur

I / We do hereby agree to do the above work @ Above / Less / At par than this Schedule Of Rates attached h	
Above / Less / At par than this schedule Of Rates attached h	erewith.
	(Signature of the Contractor)

## Page 2 of 2

	Description of Items  Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work)  Compaction factor 0.75	No. or 315.00	Unit Cum	Estimated Rate		Amount
51.				₹ 86.10	Rupees eighty six and Paise one zero Only	₹ 27,122.00
						₹ 4,81,353.00
	Total Amount put to Tender in figure #		Rupees Four Lakh eighty one Thousand three hundred			
	Total Amount put to Tender in word :	three & p			aise zero Only	

Executive Engineer
West Midnapore Division
Irrigation & Waterways Die.
Paschim Medinipur

I / We do hereby agree to do the above work @	
<u></u>	(Signature of the Contractor)