

N.I.T NO:-WBIW/ EE/ KCD-I/ NIT-01 OF 2017-18.

SL NO:-04

Schedule for the work :Removal of deposited silt from canal bed of K.M.C. (L) from Ch.-5.00 TO Ch.-28.00 of under Pirargari Sec. OF K.C. Sub- Divn. NO.-IV , Sarenga, Bankura, Under K.C. Divn. NO.-I, Amlagora, Paschim Medinipur, During - 2017-2018.

SI No	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	UNIT	AMOUNT (Rs.)
1	Cutting and removing ordinary thick or thorny jungles including clearing and depositing the same with all leads and lifts as per direction of the Engineer-in-charge	3505.20	Sqm	10.00	Sqm	35052.00
2	Earth work in excavation in canals /drainage channels/borrowpit/River bed/slope of bank as noted below as per designed section & throwing the spoils in layer of 23cm. for making banks as per profile or to deposit the same in any other place as wanted by a) Local soil/soil mixed with moorum or kankar/silt,dry or moist/slushy silt/sticky soil.	3312.73	cum	77.00	cum	255080.00
3	Extra rate over item no 1 for all kinds of soil for every additional lift of 2.00metre or part thereof beyond the initial lift of 2.00 metre. Two nos lift	3312.73	cum	2x9.00	cum	59629.00

Total = Rs . 349761.00

Rupees Three lakhs forty nine thousand seven hundred and sixty one only

Amlagora
Executive Engineer
Kangasbati Canals Divn No-I
Amlagora , Paschim Medinipur
Amlagora

I/We do here by agree to execute the above work

@.....% Above/Low/At per than the

Signature of the Contractor(s)