

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 1

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 26.20 Km to 27.00 Km along R/B of River Rupnarayan in Mouzas- Uttar Bard in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 3,00,002.00

Earnest Money : ₹ 6,000.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2000.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 15,400.00
2	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	5100.00	each	₹ 5.00	Rupees five and paise zero only	₹ 25,500.00
3	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	5100.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 32,130.00
4	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	5100.00	each	₹ 11.50	Rupees eleven and paise five zero only	₹ 58,650.00
5	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
6	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 3 (three) Extra Lead	200.00	cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 12,420.00
9	Clearing and removing weeds and water hyacinth including all leads and lifts and burning them to ashes after drying.	22090.00	sqm	₹ 5.80	Rupees five and paise eight zero only	₹ 1,28,122.00
Total Amount put to Tender in figure =						₹ 3,00,002.00
Total Amount put to Tender in word :						Rupees three lakh forty thousand eighty only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 2

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 27.10 Km to 28.00 Km along R/B of River Rupnarayan in Mouzas- Uttar Bard in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,37,537.00

Earnest Money : ₹ 2,751.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1459.30	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 11,237.00
2	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4200.00	each	₹ 5.00	Rupees five and paise zero only	₹ 21,000.00
3	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4200.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 26,460.00
4	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 4 (four) Extra Lead	4200.00	each	₹ 9.20	Rupees nine and paise two zero only	₹ 38,640.00
5	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
6	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	200.00	cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 12,420.00
Total Amount put to Tender in figure =						₹ 1,37,537.00
Total Amount put to Tender in word :						Rupees one lakh thirty seven thousand eight hundred fifty only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 3

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment at Ch. 30.00 Km along R/B of River Palaspal over Gomrai Khal in Mouzas- Nischinta pur , GP - Nischintapur in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,36,035.00

Earnest Money : ₹ 2,721.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	250.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 1,925.00
2	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2100.00	each	₹ 5.00	Rupees five and paise zero only	₹ 10,500.00
3	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2100.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 13,230.00
4	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 4 (four) Extra Lead	2100.00	each	₹ 9.20	Rupees nine and paise two zero only	₹ 19,320.00
5	Clearing and removing weeds and water hyacinth including all leads and lifts and burning them to ashes after drying.	15700.00	cum	₹ 5.80	Rupees five and paise eight zero only	₹ 91,060.00
Total Amount put to Tender in figure =						₹ 1,36,035.00
Total Amount put to Tender in word :						Rupees one lakh thirty six thousand thirty five only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 4


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 32.00 Km along L/B of River Palaspai along with sluice sealing of Kole sluice in Mouzas- Nischintapur, GP - Nischintapur in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 3,03,925.00

Earnest Money : ₹ 6,079.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	50.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 385.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	11300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 56,500.00
3	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	11300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 71,190.00
4	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	11300.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 1,55,940.00
5	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete	181.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 19,910.00
Total Amount put to Tender in figure =						₹ 3,03,925.00
Total Amount put to Tender in word :						Rupees three lakh three thousand nine hundred twenty five only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Abstract of Cost

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 5

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Mohankhali Circuit Embankment from Ch. 1.00 Km to 2.30 Km along L/B of River Durbachati in Mouzas- Dogachia, Maguria, GP - Dudkumra in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,98,369.00

Earnest Money : ₹ 5,967.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2625.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 20,213.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	567.00	m	₹ 23.60	Rupees twenty three and paise six zero only	₹ 13,381.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	378.00	m	₹ 6.30	Rupees six and paise three zero only	₹ 2,381.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	108.00	m	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,084.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	8500.00	each	₹ 5.00	Rupees five and paise zero only	₹ 42,500.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	8500.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 53,550.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	8500.00	each	₹ 11.50	Rupees eleven and paise five zero only	₹ 97,750.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	300.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 41,670.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part thereof beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 4 (Four) Extra Lead	300.00	cum	₹ 82.80	Rupees eighty two and paise eight zero only	₹ 24,840.00
Total Amount put to Tender in figure =						₹ 2,98,369.00
Total Amount put to Tender in word :						Rupees two lakh ninety eight thousand three hundred sixty nine only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 6

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Mohankhali Circuit Embankment from Ch. 2.50 Km to 3.00 Km along L/B of River Durbachati in Mouzas- Shyamganj, GP - Jote Ghanashyam in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 3,01,500.00

Earnest Money : ₹ 6,030.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	7000.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 53,900.00
2	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	4000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 20,000.00
3	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4000.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 25,200.00
4	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	4000.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 46,000.00
5	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	100.00	Cum	₹ 138.90	Rupees one thirty eight and paise nine zero only	₹ 13,890.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
6	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	100.00	Cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 6,210.00
7	Clearing and removing weeds and water hyacinth including all leads and lifts and burning them to ashes after drying.	23500.00	sqm	₹ 5.80	Rupees five and paise eight zero only	₹ 1,36,300.00
Total Amount put to Tender in figure =						₹ 3,01,500.00
Total Amount put to Tender in word :						Rupees three lakh one thousand five hundred only

Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 7

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Mohankhali Circuit Embankment from Ch. 40.00 Km to 40.50 Km along R/B of River Palaspa in Mouzas & GP - Jote ghanashyam in Block-Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 68,045.00

Earnest Money : ₹ 1,361.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	200.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 1,540.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	90.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 2,124.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	60.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 378.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	24.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 463.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	600.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 3,000.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	600.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 3,780.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 12 (twelve) Extra Lead	600.00	Each	₹ 27.60	Rupees twenty seven and paise six zero only	₹ 16,560.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated threla/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	200.00	Cum	₹ 62.10	Rupees sixty two and paise eight one zero only	₹ 12,420.00
Total Amount put to Tender in figure =						₹ 68,045.00
Total Amount put to Tender in word :						Rupees sixty eight thousand forty five only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIWEE/WMD/NIT-14 of 2017-18

Sl. No. 8

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Mohankhall Circuit Embankment from Ch. 43.00 Km to 45.00 Km along R/B of River Palaspai in Mouzas-Kultikari, GP - Dudkumra in Block-Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 4,49,018.00

Earnest Money : ₹ 8,980.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2796.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 21,529.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	378.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 8,921.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	252.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,588.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	72.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,390.00
5	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	9600.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 48,000.00
6	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	9600.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 60,480.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 4 (four) Extra Lead	9600.00	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 88,320.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	300.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 41,670.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	300.00	Cum	₹ 62.10	Rupees sixty two and paise eight one zero only	₹ 18,630.00
10	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (a) Jhama bats	99.79	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 1,49,685.00
11	Labour for spreading and consolidating jhama meta/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with hand roller/Power roller true to line and camber including carriage, cost of all materials (except jhama khaa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	66.86	Cum	₹ 131.70	Rupees sixty two and paise eight one zero only	₹ 8,805.00
Total Amount put to Tender in figure =						₹ 4,49,018.00
Total Amount put to Tender in word :						Rupees four lakh forty nine thousand eighteen only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 9

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 28.10 Km to 29.00 Km along R/B of River Rupnarayan in Mouzas- Mahis Ghata in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,70,200.00

Earnest Money : ₹ 3,404.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	180.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 1,386.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	504.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 11,894.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	336.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,117.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	96.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,853.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	5500.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 27,500.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	5500.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 34,650.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres, 4 (four) Extra Lead	5500.00	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 50,600.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	200.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	200.00	Cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 12,420.00
Total Amount put to Tender in figure =						₹ 1,70,200.00
Total Amount put to Tender in word :						Rupees one lakh seventy thousand two hundred only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 10

Schedule of Quantity, Unit, Rate and Amount for the work, "Supply of Gunny Bag at Ajuria Godown at Mouza - Ajuria, GP - Palaspai, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 75,000.00

Earnest Money : ₹ 1,500.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	15000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 75,000.00
Total Amount put to Tender in figure =						₹ 75,000.00
Total Amount put to Tender in word :						Rupees seventy five thousand only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 11

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 30.10 Km to 31.00 Km along L/B of River Palaspai in Mouzas & GP - Nischintapur in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,90,554.00

Earnest Money : ₹ 5,811.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	332.50	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 2,560.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	420.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 9,912.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	280.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,764.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	60.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,158.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	9000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 45,000.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	9000.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 56,700.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 10 (ten) Extra Lead	9000.00	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 82,800.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	200.00	Cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 12,420.00
10	Clearing and removing weeds and water hyacinth including all leads and lifts and burning them to ashes after drying.	8700.00	sqm	₹ 5.80	Rupees five and paise eight zero only	₹ 50,460.00
Total Amount put to Tender in figure =						₹ 2,90,554.00
Total Amount put to Tender in word :						Rupees two lakh ninety thousand five hundred fifty four only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 12

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment in between Ch. 29.20 Km to 30.00 Km along R/B of River Rupnarayan in Mouzas - Mahisghata GP- Kheput in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 5,50,120.00

Earnest Money : ₹ 11,002.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2763.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 21,275.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1776.25	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 41,920.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1184.17	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 7,460.00
4	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	350.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 6,755.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	15300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 76,500.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	15300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 96,390.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	15300.00	Each	₹ 13.80	Rupees nine and paise two zero only	₹ 2,11,140.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	400.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 55,560.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 4 (four) Extra Lead	400.00	Cum	₹ 82.80	Rupees sixty two and paise one zero only	₹ 33,120.00
Total Amount put to Tender in figure =						₹ 5,50,120.00
Total Amount put to Tender in word :						Rupees five lakh fifty thousand one hundred twenty only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 13

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Dussapur Circuit Embankment from Ch. 26.00 Km to 28.00 Km along L/B of River Bhosra Khal in Mouzas - Godaipur GP- Sarbaria -II In Block- Daspur- I, PS - Daspur of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 3,99,159.00

Earnest Money : ₹ 7,983.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	962.50	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 7,411.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1080.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 25,488.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	540.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,402.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	200.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,860.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	9616.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 48,080.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	9616.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 60,581.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 10 (ten) Extra Lead	9616.00	sqm	₹ 23.00	Rupees twenty three and paise zero only	₹ 2,21,168.00
8	Earthwork, transporting the earth by manually operated thela/ van/ rickshaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	210.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 29,169.00
Total Amount put to Tender in figure =						₹ 3,99,159.00
Total Amount put to Tender in word :						Rupees three lakh ninety nine thousand one hundred fifty nine only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

Abstract of Cost

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 14


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Dussaspur Circuit Embankment from Ch. 10.50 Km to 11.00 Km along L/B of River Old Cossye in Mouzas - Samatbaria GP- Nandapur-I in Block- Daspur-I, PS - Daspur of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 83,773.00

Earnest Money : ₹ 1,675.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	855.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 6,584.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	432.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 10,195.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	216.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,361.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	80.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,544.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2339.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 11,695.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2339.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 14,736.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 10 (ten) Extra Lead	2339.00	sqm	₹ 16.10	Rupees sixteen three and paise one zero only	₹ 37,658.00
Total Amount put to Tender in figure =						₹ 83,773.00
Total Amount put to Tender in word :						Rupees eighty three thousand seven hundred seventy three only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Government of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 15

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Dussaspur Circuit Embankment from Ch. 20.00 Km to 20.50 Km along L/B of River Bhosra khal in Mouzas - Paikanboalia, GP- Nandanpur -II in Block- Daspur- I, PS - Daspur of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 79,949.00

Earnest Money : ₹ 1,599.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	448.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 3,450.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	594.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 14,018.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	297.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,871.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	110.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,123.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2853.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 14,265.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2853.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 17,974.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 10 (ten) Extra Lead	2853.00	sqm	₹ 9.20	Rupees nine and paise two zero only	₹ 26,248.00
Total Amount put to Tender in figure =						₹ 79,949.00
Total Amount put to Tender in word :						Rupees seventy nine thousand nine hundred forty nine only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Abstract of Cost