

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 30

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.65.80 Km to 66.00 Km(R/S length of 50.00 Metre) along R/B of River Kanki atDafui Para in Mouza-Sitakundur, GP- Daspur in , in Block & P.S.- Daspur-I , of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 4,23,756.00

Earnest Money : ₹ 8,475.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	425.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 3,273.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameters of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	559.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 99,334.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	449.00	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 29,589.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	154.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 14,461.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	322.79	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 8,651.00
6	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	40.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 12,236.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	510.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 70,839.00
8	Extra rate in item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	510.00	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 95,013.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3600.00	each	₹ 5.00	Rupees five and paise zero only	₹ 18,000.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3600.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 22,680.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	3600.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 49,680.00
Total Amount put to Tender in figure =						₹ 4,23,756.00
Total Amount put to Tender in word :						Rupees four lakh twenty three thousand seven hundred fifty six only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dto.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 31

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.10.90 Km to 11.00 Km(R/S length of 50.00 Metre) along R/B of River Silabati at Shyamsundarpur in Mouza- Shyamsundarpur, GP- Monoharpur-II in, in Block & P.S.- Ghatal , of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 3,23,372.00

Earnest Money : ₹ 6,467.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diametre to be measured at mid length (a) Above 5 cm to 7.50 cm diametre.	1470.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 34,692.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diametre (payment will be made for driven length only) (i) Where boats are not necessary	980.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 6,174.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diametre of bamboo not less than 5 cm, to be measured at mid length)	140.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,702.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4400.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 22,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	4400.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 27,720.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	4400.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 60,720.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	520.80	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 72,339.00
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (six) Extra Lead	520.80	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 97,025.00
Total Amount put to Tender in figure =						₹ 3,23,372.00
Total Amount put to Tender in word :						Rupees three lakh twenty three thousand three hundred seventy two only

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 32

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.8.15 Km to 8.30 Km(R/S length of 40.00 Metre) along R/B of River Silabati at Goylapara in Mouza- Harisipur, GP- Monoharpur-II in , in Block & P.S.- Ghatal , of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 3,39,260.00

Earnest Money : ₹ 6,785.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	380.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 2,926.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameter of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	447.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 79,432.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	359.00	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 23,658.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	122.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 11,456.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	257.67	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 6,906.00
6	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	32.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 9,789.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ rickshaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	391.40	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 54,365.00
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	391.40	cum	₹ 186.30	Rupees one hundred eighty six and paise two zero only	₹ 72,918.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3100.00	each	₹ 5.00	Rupees five and paise zero only	₹ 15,500.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3100.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 19,530.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	3100.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 42,780.00
Total Amount put to Tender in figure =						₹ 3,39,260.00
Total Amount put to Tender in word :						Rupees three lakh thirty nine thousand two hundred sixty only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 33

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment inbetween Ch.7.15 Km to 7.30 Km(length of 50.00 Metre both side) along R/B of River Silabati at Pratapur Rathala in Mouza- Pratapur, GP- Monoharpur-II in , in Block & P.S.- Ghatal , of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 8,49,167.00

Earnest Money : ₹ 16,983.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	927.50	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 7,142.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diametere above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diametere of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diametre.	1121.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 1,99,202.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diametre.	799.50	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 52,687.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah walling pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	311.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 29,203.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	648.16	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 17,371.00
6	Fitting, fixing bitumen drum sheet to bullah piling and walling pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - In - Charge.	40.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 12,236.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. Including all lifts, as directed by the Engineer-in-charge.	1047.25	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 1,45,463.00
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	1047.25	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 1,95,103.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	7600.00	each	₹ 5.00	Rupees five and paise zero only	₹ 38,000.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	7600.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 47,880.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	7600.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 1,04,880.00
Total Amount put to Tender in figure =						₹ 8,49,167.00
Total Amount put to Tender in word :						Rupees eight lakh forty nine thousand one hundred sixty seven only

[Signature]
Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 34

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.15.80 Km to 16.00 Km(R/S length of 50.00 Metre) along R/B of River Rupnarayan at Pratapur Rathala in Mouza- Jotekanuramgar, GP-Kamalpur in , in Block -Daspur-II P.S.- Daspur , of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 4,23,234.00

Earnest Money : ₹ 8,465.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	468.50	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 3,607.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameters of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	559.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 99,334.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	449.00	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 29,589.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah walling pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	154.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 14,461.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	322.79	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 8,651.00
6	Fitting, fixing bitumen drum sheet to bullah piling and walling pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	40.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 12,236.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	491.93	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 68,329.00
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	491.93	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 91,647.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3800.00	each	₹ 5.00	Rupees five and paise zero only	₹ 19,000.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3800.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 23,940.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	3800.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 52,440.00
Total Amount put to Tender in figure =						₹ 4,23,234.00
Total Amount put to Tender in word :						Rupees four lakh twenty three thousand two hundred thirty four only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 35

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment inbetween Ch.19.80 Km to 20.00 Km(C/S length of 30.00 Metre) along R/B of River Rupnarayan at Pratapur Rathtala in Mouza & GP-Ranichak in , in Block -Daspur-II P.S.- Daspur , of Ghatal Irrigation Sub-Division under West Midnapore Division"

Amount put to Tender : ₹ 2,53,896.00
Earnest Money : ₹ 5,078.00
Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	270.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 2,079.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameters of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	338.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 60,063.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	271.50	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 17,892.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	93.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 8,733.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	195.13	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 5,229.00
6	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	24.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 7,342.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-incharge.	291.60	cum	₹ 138.90	Rupees one hundred thirteen eight and paise nine zero only	₹ 40,503.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 6 (Six) Extra Lead	291.60	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 54,325.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2300.00	each	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2300.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	2300.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 31,740.00
Total Amount put to Tender in figure =						₹ 2,53,896.00
Total Amount put to Tender in word :						Rupees two lakh fifty three thousand eight hundred ninety six only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 36

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.21.20 Km to 21.40 Km(C/S length of 30.00 Metre) along R/B of River Rupnarayan at Kojuri in Mouza & GP-Benaiin , In Block -Daspur-II P.S.- Daspur , of Ghatal Irrigation Sub-Division under West Midnapore Division".

Amount put to Tender : ₹ 2,52,841.00

Earnest Money : ₹ 5,057.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	285.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 2,195.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameters of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	338.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 60,063.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	271.50	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 17,892.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah walling pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	93.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 8,733.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	195.13	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 5,229.00
6	Fitting, fixing bitumen drum sheet to bullah piling and walling pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	24.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 7,342.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	288.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 40,003.00
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	288.00	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 53,654.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2300.00	each	₹ 5.00	Rupees five and paise zero only	₹ 11,500.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2300.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 14,490.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 15 (fifteen) Extra Lead	2300.00	each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 31,740.00
Total Amount put to Tender in figure =						₹ 2,52,841.00
Total Amount put to Tender in word :						Rupees two lakh fifty two thousand eight hundred forty one only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 37

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 57.00 Km to 60.00 Km along R/B of River Kanki in Mouzas- Jadupur, Rajnagar & Anandagarh in Block- Daspur- I, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,55,085.00

Earnest Money : ₹ 3,102.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	480.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 11,328.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	320.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 2,016.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	128.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,470.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 5,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1000.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 6,300.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	1000.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 11,500.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	382.50	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 53,129.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 8 (eight) Extra Lead	382.50	cum	₹ 165.60	Rupees one hundred sixty five and paise six zero only	₹ 63,342.00
Total Amount put to Tender in figure =						₹ 1,55,085.00
Total Amount put to Tender in word :						Rupees one lakh fifty five thousand eighty five only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 38

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 60.10 Km to 63.00 Km along R/B of River Kanki in Mouzas- Harirampur, Gurli & Suratpur in Block- Daspur- I, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 96,448.00

Earnest Money : ₹ 1,929.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	240.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 5,664.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	160.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 1,008.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	64.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,235.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	400.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 2,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	400.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 2,520.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. <u>S (five) Extra Lead</u>	400.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 4,600.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	279.85	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 38,871.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 7 (seven) Extra Lead	279.85	cum	₹ 144.90	Rupees one hundred forty four and paise nine zero only	₹ 40,550.00
Total Amount put to Tender in figure =						₹ 95,448.00
Total Amount put to Tender in word :						Rupees ninety six thousand four hundred forty eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 39

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 63.60 Km to 67.00 Km along R/B of River Kaki & Silaboti in Mouzas- Suratpur & Raghunathpur & Sitakundu in Block- Daspur- I, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,35,498.00

Earnest Money : ₹ 2,710.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	255.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 6,018.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	170.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 1,071.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	68.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,312.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 6,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 8,190.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	1300.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 14,950.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	343.40	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 47,698.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 7 (seven) Extra Lead	343.40	cum	₹ 144.90	Rupees one hundred forty four and paise nine zero only	₹ 49,759.00
Total Amount put to Tender in figure =						₹ 1,35,498.00
Total Amount put to Tender in word :						Rupees one lakh thirty five thousand four hundred ninety eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 40

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 67.20 Km to 68.7 Km along R/B of River Silaboti in Mouzas- Raghunath pur & Sujanagar in Block- Daspur- I, of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 1,54,878.00

Earnest Money : ₹ 3,098.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	765.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 18,054.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	510.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 3,213.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	180.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,474.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1600.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 8,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1600.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 10,080.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	1600.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 18,400.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	288.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 40,003.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 9 (nine) Extra Lead	288.00	cum	₹ 186.30	Rupees one hundredeighty six and paise three zero only	₹ 53,654.00
Total Amount put to Tender in figure =						₹ 1,54,878.00
Total Amount put to Tender in word :						Rupees one lakh fifty four thousand eight hundred seventy eight only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIWEE/WMD/NIT-14 of 2017-18

SL. No. 41

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 68.7 Km to 72.00 Km along R/B of River Silaboti in Mouzas- Sujanagar, Gadghat & Nimtala in Block- Daspur-I, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 3,88,027.00

Earnest Money : ₹ 7,761.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	2325.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 54,870.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1550.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 9,765.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	515.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 9,940.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	7900.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 39,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	7900.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 49,770.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	7900.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 90,850.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	410.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 56,949.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 9 (nine) Extra Lead	410.00	cum	₹ 185.30	Rupees one hundred eighty six and paise three zero only	₹ 76,383.00
Total Amount put to Tender in figure =						₹ 3,88,027.00
Total Amount put to Tender in word :						Rupees three lakh eighty eight thousand twenty seven only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIWEE/WMD/SNIT-14 of 2017-18

Sl. No. 42

Schedule of Quantity, Unit, Rate and Amount for the work "Emergent protection work of Chetua Circuit Embankment from Ch. 0.00 Km to 1.50 Km along R/B of River Silaboti in Ward No-16 & 17 in Block- Daspur- I, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 232,264.00

Earnest Money : ₹ 4,645.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	825.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 19,470.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	550.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,465.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	192.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,705.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	4300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 21,500.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	4300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 27,090.00
6	Extra rate in item no.5. above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 05(Five) nos extra lead.	4300.00	Each	₹ 11.50	Rupees thirty four and paise five zero only	₹ 49,450.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	330.82	Cum	₹ 138.90	Rupees one hundred thirty eight paise nine zero only	₹ 45,951.00
8	Extra rate for earthwork in item no. 1.01 to 1.04 above for each additional lead of 30 metres or part there of beyond the initial lead of 30 metre.					
8.1	9 (Nine) nos extra lead	330.82	Cum	₹ 186.30	Rupees sixty two and paise one zero only	₹ 61,632.00
Total Amount put to Tender in figure =						₹ 232,264.00
Total Amount put to Tender in word :						Rupees Two lakh thirty two thousand two hundred sixty four only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 43


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 1.52 Km to 2.50 Km along R/B of River Silaboti in Ward No-16 to 14 in Ghatal Municipality, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,30,920.00

Earnest Money : ₹ 4,618.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	9200.00	Mtr	₹ 5.00	Rupees five and paise zero only	₹ 46,000.00
2	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	9200.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 57,960.00
3	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	9200.00	Mtr	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 1,26,960.00
Total Amount put to Tender in figure =						₹ 2,30,920.00
Total Amount put to Tender in word :						Rupees two lakh thirty thousand nine hundred twenty only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 44


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 2.51 Km to 3.00 Km along R/B of River Silaboti in Ward No-14 to 13 in Ghatal Municipality, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 133,030.00

Earnest Money : ₹ 2,661.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
4	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	5300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 26,500.00
5	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	5300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 33,390.00
6	Extra rate in item no.5. above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6(Six) nos extra lead.	5300.00	Each	₹ 13.80	Rupees thirty four and paise five zero only	₹ 73,140.00
Total Amount put to Tender in figure =						₹ 133,030.00
Total Amount put to Tender in word :						Rupees One lakhthirty three thousand thirty only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)