

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 45

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 4.50 Km to 5.20 Km & 7.50 km to 9.00 km along R/B of River Silaboti in Mouzas- Harisinghapur, ratneswar bati & Harispur GP- Monoharpur - II in Block- Ghatal, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,42,119.00

Earnest Money : ₹ 4,842.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	540.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 12,744.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	360.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 2,268.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	108.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,084.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	8200.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 41,000.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	8200.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 51,660.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. <u>5 (five) Extra Lead</u>	8200.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 94,300.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	125.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 17,363.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 8 (eight) Extra Lead	125.00	cum	₹ 165.60	Rupees one hundred sixty five and paise six zero only	₹ 20,700.00
Total Amount put to Tender in figure =						₹ 2,42,119.00
Total Amount put to Tender in word :						Rupees two lakh forty two thousand one hundred nineteen only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 [Signature of the Contractor]

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

Sl. No. 46

GNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18
Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 9.00 Km to 13.00 Km along R/B of River Rupnarayan in Mouzas- Monoharpur-II, GP- Monoharpur-II in Block- Ghatal, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,42,229.00

Earnest Money : ₹ 4,845.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1575.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 37,170.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	1050.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 6,615.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	356.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 6,871.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3182.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 15,910.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	3182.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 20,047.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	3182.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 36,593.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	366.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 50,837.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site.	366.00	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 68,186.00
(9 (nine) Extra Lead)						₹ 2,42,229.00
Total Amount put to Tender in figure =				Rupees two lakh forty two thousand two hundred twenty nine only		
Total Amount put to Tender in word :						

[Signature]
Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

Sl. No. 47

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18
Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 13.50 Km to 17.50 Km along R/B of River Rupnarayan in Mouzas- Jote kanuram garh, Ranichack, GP- Kamalpur, Ranichack in Block- Daspur-II of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,83,769.00

Earnest Money : ₹ 3,675.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	720.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 16,992.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	480.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 3,024.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	160.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 3,088.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1427.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 7,135.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	1427.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 8,990.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	1427.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 16,411.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	394.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 54,727.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 9 (nine) Extra Lead	394.00	cum	₹ 186.30	Rupees one hundredeighty six and paise three zero only	₹ 73,402.00
Total Amount put to Tender in figure =						₹ 1,83,769.00
Total Amount put to Tender in word :						Rupees one lakh eighty three thousand seven hundred sixty nine only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 48

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 18.00 Km to 22.00 Km along R/B of River Rupnarayan in Mouza & GP- Benai, Ranichack, in Block- Daspur-II of Ghatal Irrigation Sub-Division under West Midnapore Division."


Amount put to Tender : ₹ 2,13,062.00

Earnest Money : ₹ 4,261.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1140.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 26,904.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	760.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 4,788.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	272.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 5,250.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2276.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 11,380.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2276.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 14,339.00
6	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	2276.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 26,174.00
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	382.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 53,060.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/tractors are not accessible at site. 9 (nine) Extra Lead	382.00	cum	₹ 186.30	Rupees one hundre eighty six and paise three zero only	₹ 71,167.00
Total Amount put to Tender in figure =						₹ 2,13,062.00
Total Amount put to Tender in word :						Rupees two lakh thirteen thousand sixty two only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 49

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Repairs to Forward Embankment from Jagannathpur Ghat to Kanakpur More Of L/B of River New Cossye in Mouza Jagannathpur, P.5. - Debra in the District of Paschim Medinipur.

Amount put to Tender : ₹ 481,367.00


Earnest Money : ₹ 9,627.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1152.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 27,187.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	360.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,268.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	543.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 10,480.00
4	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	6300.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 31,500.00
5	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m3/ bag.	6300.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 39,690.00
6	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	5670.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 78,246.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	6944.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 53,469.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge.	2020.00	Cum	₹ 76.70	Rupees seventy six and seven paise zero only	₹ 154,934.00
9	Extra rate for earthwork in Item no. 1.01 to 1.04 above for each additional lead of 30 metres or part thereof beyond the initial lead of 30 metre.					
9.1	5 (five) extra lead 45% of item 8	909.00	Cum	₹ 38.50	Rupees thirty eight and paise five zero only	₹ 34,997.00
9.2	6 (six) extra lead 45% of item 8	909.00	Cum	₹ 46.20	Rupees forty six and paise two zero only	₹ 41,996.00
10	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	60.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 6,600.00
Total Amount put to Tender in figure =						₹ 481,367.00
Total Amount put to Tender in word :						Rupees four lakh eighty one thousand three hundred sixty seven only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 [Signature of the Contractor]

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 50


Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Supply of Nylon cage net to Khanamohan Section of Lachmapur(I) Sub-Division under West Midnapore Division during 2017-18.

Amount put to Tender : ₹ 110,000.00

Earnest Money : ₹ 2,200.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	1000.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 110,000.00
Total Amount put to Tender in figure =						₹ 110,000.00
Total Amount put to Tender in word :						Rupees one lakh ten thousand only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 51

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Supply of 2nd hand cement Poly bags to Khanamohan Section of Lachmapur(I) Sub-Division under West Midnapore Division during 2017-18.

Amount put to Tender : ₹ 150,000.00

Earnest Money : ₹ 3,000.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	30000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 150,000.00
Total Amount put to Tender in figure =						₹ 150,000.00
Total Amount put to Tender in word :						Rupees one lakh fifty thousand only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 52

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent repairs of bank along with Country side backing at ch. 35.60 [Working length 120.00 M] of TE1H1 embankment of R/B of New Cossye River under Khanamohan (I) Section of Lachmapur (I) Sub-Division.

Amount put to Tender : ₹ 928,568.00

Earnest Money : ₹ 18,571.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameter of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete.	1205.00	Mtr.	₹ 185.60	Rupees one hundred eighty five and paise six zero only	₹ 223,648.00
2	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground.	916.00	Mtr.	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 60,364.00
3	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah walling pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (b) Above 12.50 cm & up to 15.00 cm.	360.00	Mtr.	₹ 78.80	Rupees seventy eight and paise eight zero only	₹ 28,368.00
4	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	720.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 16,992.00
5	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	288.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,814.00
6	Fitting, fixing bitumen drum sheet to bullah piling and walling pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	144.00	Sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 44,050.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ rickshaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	1080.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 150,012.00
8	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	360.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 39,600.00
9	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	16800.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 84,000.00
10	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	16800.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 105,840.00
11	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	15120.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 173,880.00
Total Amount put to Tender in figure =						₹ 928,568.00
Total Amount put to Tender in word :						Rupees nine lakh twenty eight thousand five hundred sixty eight only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Abstract of Cost

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

SI. No. 53

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Repairs to slip at ch. 1.45 km. at R/S & C/S backing at ch. 1.80 km. of TE2H2 Embankment Of R/B of River Old Cossye in Mouza Baikunthapur, P.S. - Debra in the District of Paschim Medinipur.

Amount put to Tender : ₹ 285,422.00

Earnest Money : ₹ 5,708.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1540.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 36,344.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	595.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,749.00
3	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	660.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 12,738.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	5250.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 26,250.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	5250.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 33,075.00
6	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	4725.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 65,205.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	350.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 2,695.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge.	511.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 70,978.00
9	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	70.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 7,700.00
10	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer - in - charge. (measurement to be made on volume of each bundle)	480.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 26,688.00
Total Amount put to Tender in figure =						₹ 285,422.00
Total Amount put to Tender in word :						Rupees two lakh eighty five thousand four hundred twenty two only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 54

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repairs to rain cuts, verticals, slips in between Ch-26.40 Km. & 29.00 Km. of TE1H1 embktt damaged due to incessant rainfall from 22.07.17 to 24.07.17, R/B of River New Cossye under West Midnapore Division during the year 2017-18

Amount put to Tender : ₹ 335,406.00

Earnest Money : ₹ 6,708.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-	12480.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 96,096.00
2	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	322.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 44,726.00
3	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (b) Jhama bats	82.00	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 123,000.00
	(g) Moorum	65.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 35,100.00
4	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials (a) For a distance above 20 km and up to 50 km (per km).	65.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 18,525.00
	(b) For a distance above 50 km and up to 100 km (per km).	65.00	Cum	₹ 100.80	Rupees one hundred and paise eight zero only	₹ 6,552.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
5	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoas) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.57	54.68	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 7,201.00
6	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	48.85	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 4,206.00
Total Amount put to Tender in figure =						₹ 335,406.00
Total Amount put to Tender in word :						Rupees three lakh thirty five thousand four hundred six only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 [Signature of the Contractor]

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 55

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent repairs to both bank in between ch.3.00 km to 5.30 km. of Dy-E of 3 Main canal of M.M.C., damaged due to incessant rainfall from 22.07.17 to 24.07.17, [Mouza- Panchgeria, Jesua] under West Midnapore Division during the year 2016-17."

Amount put to Tender : ₹ 618,009.00


Earnest Money : ₹ 12,360.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-	10710.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 82,467.00
2	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	52.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 7,223.00
3	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (b) Jhama bats	116.00	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 174,000.00
	(g) Moorum	266.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 143,640.00
4	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials (a) For a distance above 20 km and up to 50 km (per km).	266.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 75,810.00
	(b) For a distance above 50 km and up to 100 km (per km).	266.00	Cum	₹ 58.80	Rupees one hundred and paise eight zero only	₹ 15,641.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
5	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer-in - Charge. (measurement to be made on finished work) Compaction factor 0.67	77.15	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 10,161.00
6	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- In - Charge. (measurement to be made on finished work) Compaction factor 0.75	199.15	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 17,147.00
7	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	1170.00	Mtr.	₹ 23.50	Rupees twenty three and paise six zero only	₹ 27,612.00
8	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	585.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 3,686.00
9	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	260.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 5,018.00
10	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	3134	Each	₹ 5.00	Rupees five and paise zero only	₹ 15,670.00
11	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m ³ / bag.	3134	Each	₹ 6.30	Rupees six and paise three zero only	₹ 19,744.00
12	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. A) 3 (Three) extra lead	1254	Each	₹ 6.90	Rupees six and paise nine zero only	₹ 8,553.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
	b) 4 (Four) extra lead	1254	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 11,537.00
Total Amount put to Tender in figure =						₹ 518,009.00
Total Amount put to Tender in word :						Rupees three lakh thirty five thousand four hundred six only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 56

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent repairs to both bank inbetween ch.3.50 km to 5.80 km. & Jungle clearance inbetween ch. 0.00 km to 5.80 km. of Dy- D of 3 Main canal of M.M.C.[Mouza-Shyamsundarpur,Gopinathpur,Benia, Satkona] damaged due to incessant rainfall from 22.07.17 to 24.07.17, under West Midnapore Division during the year 2016-17.*

Amount put to Tender : ₹ 459,466.00

Earnest Money : ₹ 9,189.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-	8120.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 62,524.00
2	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	85.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 11,807.00
3	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (b) Jhama bats	82.00	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 123,000.00
	(g) Moorum	226.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 122,040.00
4	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials (a) For a distance above 20 km and up to 50 km (per km).	226.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 64,410.00
	(b) For a distance above 50 km and up to 100 km (per km).	226.00	Cum	₹ 50.40	Rupees fifty and paise four zero only	₹ 11,390.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
5	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	54.87	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 7,226.00
6	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen shoulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	169.40	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 14,585.00
7	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length (a) Above 5 cm to 7.50 cm diameter.	540.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 12,744.00
8	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	270.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,701.00
9	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm. to be measured at mid length)	120.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 2,316.00
10	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	1450.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 7,250.00
11	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m3/ bag.	1450.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 9,135.00
12	Extra rate in Item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. A) 3 (Three) extra lead	580.00	Each	₹ 6.90	Rupees six and paise nine zero only	₹ 4,002.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
	b) 4 (Four) extra lead	580.00	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 5,336.00
Total Amount put to Tender in figure =						₹ 459,466.00
Total Amount put to Tender in word :						Rupees four lakh fifty nine thousand four hundred sixty six only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dte.
 Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

 (Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

SL No. 57

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repairs to raincuts, Varitical, slip, in between Ch.-30.50 Km. & 31.50 Km. of TE1H1 embankment of R/B of River New Cossye in P.S.- Debra in the district of Paschim Medinipur.

Amount put to Tender : ₹ 351,930.00

Earnest Money : ₹ 7,039.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an	650.00	Cum.	₹ 76.70	Rupees Seventy six and paise seven zero only	₹ 49,855.00
2	Extra rate for earthwork in Item no. 1.01 to 1.04 above for each additional lead of 30 metres or part thereof beyond the initial lead of 30 metre. 6 (six) extra lead.	450.00	Cum.	₹ 46.20	Rupees Forty six and paise two zero only	₹ 20,790.00
3	Extra rate for earthwork in Item no. 1.01 to 1.04 above for each additional lift of 1.5 metres or part thereof beyond the initial lift of 1.5 metre. 1 (One) extra lift.	650.00	Cum.	₹ 4.60	Rupees four and paise six zero only	₹ 2,990.00
4	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. <u>h. Laterite chelly.</u>	90.00	Cum.	₹ 857.90	Rupees eight hundred fifty seven and paise nine zero only	₹ 77,211.00
	<u>(g) Moorum</u>	160.00	Cum.	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 86,400.00
5	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials (a) For a distance above 20 km and up to 50 km (per km) = 30 Km. extra lead.	250.00	Cum.	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 71,250.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
	b) For a distance above 50 km. & upto 100km, 12 km. extra lead	250.00	Cum.	₹ 100.80	Rupees One hundred and paise eight zero only	₹ 25,200.00
6	<u>[Page no-32, Item - 7.13 of WC-II, I & W Dtg.]</u> Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kila rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67.	60.00	Cum.	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 7,902.00
7	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	120.00	Cum.	₹ 86.10	Rupees eighty six and paise one zero only	₹ 10,332.00
Total Amount put to Tender in figure =						₹ 351,930.00
Total Amount put to Tender in word :						Rupees four lakh one thousand six hundred eighty four only


 Executive Engineer
 West Midnapore Division
 Irrigation & Waterways Dto.
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Abstract of Cost

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 58


Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Supply of 2nd hand cement Poly bags to Anicut Section of Lachmapur(I) Sub-Division under West Midnapore Division during 2017-18.

Amount put to Tender : ₹ 150,000.00

Earnest Money : ₹ 3,000.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	30000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 150,000.00
Total Amount put to Tender in figure =						₹ 150,000.00
Total Amount put to Tender in word :						Rupees one lakh fifty thousand only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Abstract of Cost

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No.59

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Supply of 2nd hand cement Poly bags to Anicut Hd. Quarter Section of Lachmapur(I) Sub-Division under West Midnapore Division during 2017-18.

Amount put to Tender : ₹ 150,000.00

Earnest Money : ₹ 3,000.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	30000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 150,000.00
Total Amount put to Tender in figure =						₹ 150,000.00
Total Amount put to Tender in word :						Rupees one lakh fifty thousand only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 60


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repair of moorum inspection road in between Ch. 70.00 Km & 71.60 Km along R/B of river Silaboti in mouzas-Nimtala, rasikgang, Gadghat, GP - Daspur - I Block- Daspur- I, PS - Daspur of Ghatal Irrigation Sub-Division within West Midnapore Division."

Amount put to Tender : ₹ 9,92,235.00

Earnest Money : ₹ 19,845.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (a) Jhama bats	97.03	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 1,45,545.00
	(b) Moorum	640.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 3,45,600.00
2	Extra rate over carriage of sand, moorum, brick bats, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials For distance 112.50 Km: (a) For a distance above 20 km and up to 50 km (per km). - 30.00 (thirty) Km extra lead	640.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 1,82,400.00
	(b) For a distance above 50 km and up to 92 km (per km). - 50.00 (fifty) Km extra lead	640.00	Cum	₹ 420.00	Rupees four hundred twenty and paise zero only	₹ 2,68,800.00
3	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with hand roller/Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	65.01	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 8,562.00
4	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	480.00	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 41,328.00
Total Amount put to Tender in figure =						₹ 9,92,235.00
Total Amount put to Tender in word :						Rupees nine lakh ninety two thousand two hundred thirty five only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

Abstract of Cost

(Signature of the Contractor)

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 61


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repair of moorum Inspection road in between Ch. 4.35 Km & 5.15 Km along R/B of river Silaboti in mouzasKonnagar, Harisingpur, Pratapur, GP - Monoharpur - II Block- & PS - Ghatal of Ghatal Irrigation Sub-Division within West Midnapore Division."

Amount put to Tender : ₹ 9,59,750.00

Earnest Money : ₹ 19,195.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (Inclusive of all taxes) as per direction of the Engineer-in-charge. (a) Jhama bats	287.66	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 4,31,490.00
	(b) Moorum	384.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 2,07,360.00
2	Extra rate over carriage of sand, moorum, brick bats, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials For distance 112.50 Km: (a) For a distance above 20 km and up to 50 km (per km). - 30.00 (thirty) Km extra lead	384.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 1,09,440.00
	(b) For a distance above 50 km and up to 92 km (per km). - 50.00 (fifty) Km extra lead	384.00	Cum	₹ 420.00	Rupees four hundred twenty and paise zero only	₹ 1,61,280.00
3	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with hand roller/Power roller true to line and camber including carriage, cost of all materials (except jhama khoaj) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	192.73	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 25,383.00
4	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	288.00	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 24,797.00
Total Amount put to Tender in figure =						₹ 9,59,750.00
Total Amount put to Tender in word :						Rupees nine lakh fifty nine thousand seven hundred fifty only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

Abstract of Cost

(Signature of the Contractor)

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 62


Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repair of moorum inspection road in between Ch. 5.20 Km & 5.80 Km along R/B of river Silaboti in mouzas Konnagar, Harisingpur, Pratapur, GP - Monoharpur - II Block- & PS - Ghatal of Ghatal Irrigation Sub-Division within West Midnapore Division."

Amount put to Tender : ₹ 7,19,789.00

Earnest Money : ₹ 14,396.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (a) Jhama bats	215.73	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 3,23,595.00
	(b) Moorum	288.00	Cum	₹ 540.00	Rupees five hundred forty and paise zero only	₹ 1,55,520.00
2	Extra rate over carriage of sand, moorum, brick bats, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials For distance 112.50 Km: (a) For a distance above 20 km and up to 50 km (per km). - 30.00 (thirty) Km extra lead	288.00	Cum	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 82,080.00
	(b) For a distance above 50 km and up to 92 km (per km). - 50.00 (fifty) Km extra lead	288.00	Cum	₹ 420.00	Rupees four hundred twenty and paise zero only	₹ 1,20,960.00
3	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with hand roller/Power roller true to line and camber including carriage, cost of all materials (except jhama khoal) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	144.54	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 19,036.00
4	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	216.00	Cum	₹ 86.10	Rupees eighty six and paise one zero only	₹ 18,598.00
Total Amount put to Tender in figure =						₹ 7,19,789.00
Total Amount put to Tender in word : Rupees seven lakh nineteen thousand seven hundred eighty nine only						


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @

Above / Less / At par than this Schedule Of Rates attached herewith.

Abstract of Cost

(Signature of the Contractor)

Govt. of West Bengal
Irrigation & Waterways Dte.
Office of the Executive Engineer
West Midnapore Division
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 63

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent repairs to raincuts, Varitical, slip, mending damages from Ch.-30.00 Km. to 30.450 Km. of TE1H1 embankment of R/B of River New Cossye in P.S.- Debra in the district of Paschim Medinipur.

Amount put to Tender : ₹ 577,248.00


Earnest Money : ₹ 11,545.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an	1073.00	Cum.	₹ 76.70	Rupees Seventy six and paise seven zero only	₹ 82,299.00
2	Extra rate for earthwork in Item no. 1.01 to 1.04 above for each additional lead of 30 metres or part thereof beyond the initial lead of 30 metre. 6 (six) extra lead.	966.00	Cum.	₹ 46.20	Rupees Fourty six and paise two zero only	₹ 44,629.00
3	Extra rate for earthwork in Item no. 1.01 to 1.04 above for each additional lift of 1.5 metres or part thereof beyond the initial lift of 1.5 metre. 1 (One) extra lift.	966.00	Cum.	₹ 4.60	Rupees four and paise six zero only	₹ 4,444.00
4	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. <u>h. Jhama hats.</u>	161.00	Cum.	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 241,500.00
	<u>(g) Moorum</u>	192.00	Cum.	₹ 540.00	Rupees five hundred fourty and paise zero only	₹ 103,680.00
5	Extra rate over carriage of sand, moorum, boulder, stone metal, stone chips, gravel, slag metal, shingle and similar materials (n) For a distance above 20 km and up to 50 km (per km) = 30 Km. extra lead.	192.00	Cum.	₹ 285.00	Rupees two hundred eighty five and paise zero only	₹ 54,720.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
	b) For a distance above 50 km. & upto 100km. 12 km. extra lead	192.00	Cum.	₹ 100.80	Rupees One hundred and paise eight zero only	₹ 19,354.00
6	<u>[Page no-32, Item - 7.13 of WC-II, I & W Dte.]</u> Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67.	108.00	Cum.	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 14,224.00
7	Labour for spreading moorum to proper level including hand packing and consolidation by hand roller / power roller of specified thickness in layer after watering etc. complete with necessary earthen soulder as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.75	144.00	Cum.	₹ 86.10	Rupees eighty six and paise one zero only	₹ 12,398.00
Total Amount put to Tender in figure =						₹ 577,248.00
Total Amount put to Tender in word :						Rupees five lakh seventy seven thousand two hundred forty eight only


Executive Engineer
West Midnapore Division
Irrigation & Waterways Dte.
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)