

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 64

Schedule of Quantity, Unit, Rate and Amount for the work, Emergent Repairs to slip at ch. 15.40 km. at R/S & C/S backing of TE3H2 Embankment Of L/B of River NeW Cossye in Mouza Kamalpur, P.S. - Debra in the District of Paschim Medinipur.

Amount put to Tender : ₹ 302,441.00  
Earnest Money : ₹ 6,049.00  
Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	1260.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 29,736.00
2	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	420.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,646.00
3	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	560.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 10,808.00
4	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	6200.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 31,000.00
5	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be less than 0.028 m <sup>3</sup> / bag.	6200.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 39,060.00
6	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres.	5580.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 77,004.00
7	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	2240.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 17,248.00

Abstract of Cost

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling zone etc. complete as per direction of Engineer-in-charge.	532.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 73,895.00
9	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete.	70.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 7,700.00
10	Supplying brush wood including tying them in bundles with 12 SWG galvanized wire filling in specified areas in bundles and providing ties with half split bamboos fitted, fixed including lead upto 2 km and all lifts, laying and placing complete as per direction of the Engineer - in - charge. (measurement to be made on volume of each bundle)	240.00	Cum	₹ 55.60	Rupees fifty five and paise six zero only	₹ 13,344.00
Total Amount put to Tender in figure =						₹ 302,441.00
Total Amount put to Tender in word :						Rupees three lakh two thousand four hundred forty one only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIWEE/WMD/NIT-14 of 2017-18

Sl. No. 65

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent restoration work of Ratanpur canal of 1-Main canal damaged due to incessant rainfall from 22.07.17 to 24.07.17, under West Midnapore Division during the year 2017-18.

Amount put to Tender : ₹ 437,717.00

Earnest Money : ₹ 8,754.00


Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling Zone etc complete as per direction of Engineer in charge.	630.00	Cum	₹ 76.70	Rupees seventy six and paise seven zero only	₹ 48,321.00
2	Extra rate for earthwork in item no-1.01 above for each additional lead of 30 metres or part thereof beyond the initial lead of 30 metre [4 Extra lead]	630.00	Cum	₹ 30.80	Rupees thirty and paise eight zero only	₹ 19,404.00
3	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	24480.00	Sqm.	₹ 7.70	Rupees seven and paise seven zero only	₹ 188,496.00
4	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	8223.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 41,115.00
5	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be	8223.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 51,805.00

Abstract of Cost



Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
6	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. A) 2 (Two) extra lead	8223.00	Each	₹ 4.60	Rupees four and paise six zero only	₹ 37,826.00
7	Dumping in position earth filled poly bags inclusive of all leads and lifts. (admissible only when placed under flowing water.)	8223.00	Each	₹ 2.30	Rupees two and paise three zero only	₹ 18,913.00
8	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	972.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 22,939.00
9	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	432.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,722.00
10	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	320.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 6,176.00
Total Amount put to Tender in figure =						₹ 437,717.00
Total Amount put to Tender in word :						Rupees four lakh thirty seven thousand seven hundred seventeen only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 66

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment inbetween Ch.69.8.00 Km to 70.00 Km along R/B of River Silabati at Ghorol Para in Mouza - Gadghat GP- Daspur, in Block -Daspur-I P.S.- Daspur, of Ghatal Irrigation Sub-Division under West Midnapore Division"


Amount put to Tender : ₹ 6,27,521.00

Earnest Money : ₹ 12,550.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	712.50	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 5,486.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameter of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	833.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 1,48,024.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	669.00	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 44,087.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	228.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 21,409.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	480.43	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 12,876.00
6	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	60.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 18,354.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	712.50	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 98,966.00
8	Extra rate in item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	712.50	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 1,32,739.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	5800.00	each	₹ 5.00	Rupees five and paise zero only	₹ 29,000.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	5800.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 36,540.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	5800.00	each	₹ 13.80	Rupees thirteen and paise eighty only	₹ 80,040.00
Total Amount put to Tender in figure =						₹ 6,27,521.00
Total Amount put to Tender in word :						Rupees six lakh twenty seven thousand five hundred twenty one only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)



Govt. of West Bengal  
Irrigation & Waterways Dto.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 67

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment Inbetween Ch.0.20 Km to 0.50 Km along R/B of River Silabati at Barik Para in Ward no-17 Ghatal Municipality, in Block & P.S. -Ghatal of Ghatal Irrigation Sub-Division under West Midnapore Division"

Amount put to Tender : ₹ 5,85,155.00

Earnest Money : ₹ 11,703.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	665.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 5,121.00
2	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameter of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 15.00 cm. Av. Diameter.	777.00	Mtr	₹ 177.70	Rupees one hundred seventy seven and paise seven zero only	₹ 1,38,073.00
3	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening, driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 10cm to 15 cm Av. Diameter.	624.00	Mtr	₹ 65.90	Rupees sixty five and paise nine zero only	₹ 41,122.00
4	Supplying and fitting fixing with iron nails, half split Eucalyptus Bullah wailing pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	212.00	Mtr	₹ 93.90	Rupees ninety three and paise nine zero only	₹ 19,907.00
5	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	447.87	Sqm	₹ 26.80	Rupees twenty six and paise eight zero only	₹ 12,003.00
6	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	56.00	sqm	₹ 305.90	Rupees three hundred five and paise nine zero only	₹ 17,130.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
7	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	665.00	cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 92,369.00
8	Extra rate in Item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 6 (Six) Extra Lead	665.00	cum	₹ 186.30	Rupees one hundred eighty six and paise three zero only	₹ 1,23,890.00
9	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	5400.00	each	₹ 5.00	Rupees five and paise zero only	₹ 27,000.00
10	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	5400.00	each	₹ 6.30	Rupees six and paise three zero only	₹ 34,020.00
11	Extra rate in Sl. no. 10 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	5400.00	each	₹ 13.80	Rupees thirteen and paise eighty only	₹ 74,520.00
Total Amount put to Tender in figure =						₹ 5,85,155.00
Total Amount put to Tender in word :						Rupees five lakh eighty five thousand one hundred fifty five only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @ .....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
 (Signature of the Contractor)



Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/SNIT-14 of 2017-18

Sl. No. 68

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent restoration work of Swargeria canal of 1-Main canal damaged due to incessant rainfall from 22.07.17 to 24.07.17, under West Midnapore Division during the year 2017-18.


Amount put to Tender : ₹ 360,150.00

Earnest Money : ₹ 7,203.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Earthwork in excavation by any means from borrowpits, canals and channels in all kinds of soil for maintenance and repairs of embankments, canals, channels and roads as per profile within an initial lead of 30 metres and lift of 1.50 metre including breaking clods, rough dressing, including removal of jungles and trees upto 30 cm. girth in both cutting and filling Zone etc complete as per direction of Engineer in charge.	630.00	Cum	₹ 76.70	Rupees seventy six and paise seven zero only	₹ 48,321.00
2	Extra rate for earthwork in item no-1.01 above for each additional lead of 30 metres or part thereof beyond the initial lead of 30 metre [4 Extra lead]	630.00	Cum	₹ 30.80	Rupees thirty and paise eight zero only	₹ 19,404.00
3	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	14976.00	Sqm.	₹ 7.70	Rupees seven and paise seven zero only	₹ 115,315.00
4	Supplying to site 2nd hand cement poly bags in good condition delivered and stacked (capacity 50 kg).	7982.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 39,910.00
5	Labour charge for filling poly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge. NB:- Volume of earth/ sand filled bags should not be	7982.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 50,287.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
6	Extra rate in item no. 4.02 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. A) 2 (Two) extra lead	7982.00	Each	₹ 4.60	Rupees four and paise six zero only	₹ 36,717.00
7	Dumping in position earth filled poly bags inclusive of all leads and lifts. (admissible only when placed under flowing water.)	7982.00	Each	₹ 2.30	Rupees two and paise three zero only	₹ 18,359.00
8	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	972.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 22,939.00
9	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary a) Not less than 5 Cm. Av. Diameter	432.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 2,722.00
10	Supplying, fitting, fixing with iron nails, half split bamboo walling pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	320.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 6,175.00
Total Amount put to Tender in figure =						₹ 360,150.00
Total Amount put to Tender in word :						Rupees three lakh sixty thousand one hundred fifty only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 69

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection of Mohankhali Circuit Embankment in between Ch. 35.00 Km to 36.00 Km along R/B of River Palaspai in Mouzas- Sitapur, GP - Gaura, in Block- Daspur-II, under Ajuria Section of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 1,12,932.00

Earnest Money : ₹ 2,259.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	1440.00	sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 11,088.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	306.00	Mtr.	₹ 23.60	Rupees twenty three and paise six zero only	₹ 7,222.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	204.00	Mtr.	₹ 6.30	Rupees six and paise three zero only	₹ 1,285.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	68.00	Mtr.	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,312.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	2273.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 11,365.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags. (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	2273.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 14,320.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 5 (five) Extra Lead	2273.00	Each	₹ 11.50	Rupees eleven and paise five zero only	₹ 26,140.00



Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	200.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 27,780.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	200.00	Cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 12,420.00
Total Amount put to Tender in figure =						₹ 1,12,932.00
Total Amount put to Tender in word :						Rupees one lakh twelve thousand nine hundred thirty two only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dto.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 70


Schedule of Quantity, Unit, Rate and Amount for the work, "Supply Pump for dewatering of flood water at Mouza - Palaspai near Kali Manir, GP- Palaspai of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 7,93,408.00

Earnest Money : ₹ 15,868.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Dewatering by pumps within all lifts and making all arrangements for disposal of the same upto a specified istance, where continuous flow or seepage of water is encountered, as directed. The rating of pumps and hours of operations is ascertained as per direction of the Engineer-in-charge.	25760.00	Hp.Hr.	₹ 30.80	Rupees thirty and paise eight zero only	₹ 7,93,408.00
Total Amount put to Tender in figure =						₹ 7,93,408.00
Total Amount put to Tender in word :						Rupees seven lakh ninety three thousand four hundred eight only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @ .....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

SNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 71


Schedule of Quantity, Unit, Rate and Amount for the work, "Supply Pump for dewatering of flood water at Mouza - Palaspai near Prymary School , GP- Palaspai of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 7,43,820.00

Earnest Money : ₹ 14,876.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Dewatering by pumps within all lifts and making all arrangements for disposal of the same upto a specified listance, where continuous flow or seepage of water is encountered, as directed. The rating of pumps and hours of operations is ascertained as per direction of the Engineer-in-charge.	24150.00	Hp.Hr.	₹ 30.80	Rupees thirty and paise eight zero only	₹ 7,43,820.00
Total Amount put to Tender in figure =						₹ 7,43,820.00
Total Amount put to Tender in word :						Rupees seven lakh forty three thousand eight hundred twenty only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @ .....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)



Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 72


Schedule of Quantity, Unit, Rate and Amount for the work, "Supply Pump for dewatering of flood water at Mouza - Benal near Ghata Para, GP- Palaspai of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 8,92,584.00

Earnest Money : ₹ 17,852.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Dewatering by pumps within all lifts and making all arrangements for disposal of the same upto a specified istance, where continuous flow or seepage of water is encountered, as directed. The rating of pumps and hours of operations is ascertained as per direction of the Engineer-in-charge.	28980.00	Hp.Hr.	₹ 30.80	Rupees thirty and paise eight zero only	₹ 8,92,584.00
Total Amount put to Tender in figure =						₹ 8,92,584.00
Total Amount put to Tender in word :						Rupees eight lakh ninety two thousand five hundred eighty four only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

S/NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 73


Schedule of Quantity, Unit, Rate and Amount for the work, "Supply Pump for dewatering of flood water at Mouza - Benai near Sekh Para, GP- Palaspai of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 8,50,080.00

Earnest Money : ₹ 17,002.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Dewatering by pumps within all lifts and making all arrangements for disposal of the same upto a specified istance, where continuous flow or seepage of water is encountered, as directed. The rating of pumps and hours of operations is ascertained as per direction of the Engineer-in-charge.	27600.00	Hp.Hr.	₹ 30.80	Rupees thirty and paise eight zero only	₹ 8,50,080.00
Total Amount put to Tender in figure =						₹ 8,50,080.00
Total Amount put to Tender in word :				Rupees eight lakh fifty thousand eighty only		

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)

Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 74

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment at Ch. 26.10 Km along R/B of River Rupnarayan along with sluice sealing of New Chandreswar sluice in Mouzas - Uttarbar GP - Kheput In Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 2,55,700.00

Earnest Money : ₹ 5,114.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	9600.00	Each	₹ 5.00	Rupees live and paise zero only	₹ 48,000.00
2	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	9600.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 60,480.00
3	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	9600.00	Each	₹ 13.80	Rupees thirteen and paise eight zero only	₹ 1,32,480.00
4	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete	134.00	Each	₹ 110.00	Rupees one hundred ten and paise zero only	₹ 14,740.00
Total Amount put to Tender in figure =						₹ 2,55,700.00
Total Amount put to Tender in word :						Rupees two lakh fifty five thousand seven hundred only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

(Signature of the Contractor)



Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

NIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 75

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Mohankhali Circuit Embankment from Ch. 41.00 Km to 42.50 Km along R/B of River Palaspai in Mouzas-Jote ghanashyam, GP -Jote ghanashyam in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 4,73,587.00

Earnest Money : ₹ 9,472.00

Time allowed for Completion : 15 Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Uprooting, clearing and cleaning all types of thick and thorny jungles, including trees upto 30 cm girth with stumps and removing them beyond working zone and burning to ashes as per direction of the Engineer-in-charge.	3650.00	Sqm	₹ 7.70	Rupees seven and paise seven zero only	₹ 28,182.00
2	Supplying, dressing and stacking at site bamboo pins (diameter to be measured at mid length) (a) Above 5 cm to 7.50 cm diameter.	378.00	Mtr	₹ 23.60	Rupees twenty three and paise six zero only	₹ 8,921.00
3	Driving bamboo pins of average 5 cm to 7.5 cm diameter (payment will be made for driven length only) (i) Where boats are not necessary	252.00	Mtr	₹ 6.30	Rupees six and paise three zero only	₹ 1,588.00
4	Supplying, fitting, fixing with iron nails, half split bamboo wailing pieces. (Diameter of bamboo not less than 5 cm, to be measured at mid length)	72.00	Mtr	₹ 19.30	Rupees nineteen and paise three zero only	₹ 1,390.00
5	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	11000.00	Each	₹ 5.00	Rupees five and paise zero only	₹ 55,000.00
6	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	11000.00	Each	₹ 6.30	Rupees six and paise three zero only	₹ 69,300.00
7	Extra rate in Sl. No. 6 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 4 (four) Extra Lead	11000.00	Each	₹ 9.20	Rupees nine and paise two zero only	₹ 1,01,200.00

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	300.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 41,670.00
9	Extra rate in Sl. No. 8 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 3 (three) Extra Lead	300.00	Cum	₹ 62.10	Rupees sixty two and paise one zero only	₹ 18,630.00
10	Supplying of materials to site including cost of loading, carriage upto 20 km, unloading and stacking (inclusive of all taxes) as per direction of the Engineer-in-charge. (a) Jhama bats	93.00	Cum	₹ 1,500.00	Rupees one thousand five hundred and paise zero only	₹ 1,39,500.00
11	Labour for spreading and consolidating jhama metal/ 1st class Brick bats / laterite chelly of specific size to requisite thickness in layers including spreading with kiln rubbish, hand packing, watering and compacting with hand roller/Power roller true to line and camber including carriage, cost of all materials (except jhama khoa) and hire charges of all equipments as per direction of the Engineer- in - Charge. (measurement to be made on finished work) Compaction factor 0.67	62.31	Cum	₹ 131.70	Rupees one hundred thirty one and paise seven zero only	₹ 8,206.00
Total Amount put to Tender in figure =						₹ 4,73,587.00
Total Amount put to Tender in word :						Rupees four lakh seventy three thousand five hundred eighty seven only

  
 Executive Engineer  
 West Midnapore Division  
 Irrigation & Waterways Dte.  
 Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)



Page 1 of 2  
Govt. of West Bengal  
Irrigation & Waterways Dte.  
Office of the Executive Engineer  
West Midnapore Division  
Medinipur, Paschim Medinipur

JNIT NO- WBIW/EE/WMD/NIT-14 of 2017-18

Sl. No. 76

Schedule of Quantity, Unit, Rate and Amount for the work, "Emergent protection work of Chetua Circuit Embankment from Ch. 25.00 Km along L/B of River Rupnarayan along with sluice protection of Benal sluice in Mouzas & GP - Benal in Block- Daspur- II, of Ghatal Irrigation Sub-Division under West Midnapore Division."

Amount put to Tender : ₹ 4,66,467.00


Earnest Money : ₹ 9,329.00

Time allowed for Completion : Days

Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
1	Supplying to site 2nd hand cement polly bags in good condition delivered and stacked (capacity 50 kg).	6600.00	Each	₹ 5.00	Rupees seven and paise seven zero only	₹ 33,000.00
2	Labour charge for filling polly bags (capacity 50 kg cement bag) with all kinds of earth (wet or dry) or sand including sewing the mouth after filling (cost of thread included), as done in case of cement bags, (tying with a knot after filling will not be accepted) and placing in position within an initial lead of 150 metres including cost of excavation of earth as per direction of the Engineer-in-charge.	6600.00	Each	₹ 6.30	Rupees twenty three and paise six zero only	₹ 41,580.00
3	Extra rate in Sl. No. 2 above for each additional lead of 60 metres or part thereof over initial lead of 150 metres. 6 (six) Extra Lead	6600.00	Each	₹ 13.80	Rupees six and paise three zero only	₹ 91,080.00
4	Supplying Nylon cage netting 1 metre x 1 metre x 1 metre size with knot having mesh size 17.5 cm x 17.5 cm constructed with nylon thread (210 x 24) having tensile strength not less than 250 Kg. / sq. cm. including carriage, delivery and stacking at site inclusive of all taxes complete	132.00	Each	₹ 110.00	Rupees nineteen and paise three zero only	₹ 14,520.00
5	Supplying Eucalyptus bullah at site including sizing and sharpening one end and dressing the other end for driving (bigger diameters above specified size if supplied shall be paid at the rate of specified diameter). Measurement of diameters of bullah will be at 1/3rd from the thicker end and without bark) including loading, unloading, carriage at site complete. (a) 17.50 cm. Av. Diameter	407.00	Mtr	₹ 228.20	Rupees five and paise zero only	₹ 92,877.00
6	Labour for driving Eucalyptus bullah piles by monkey in all sorts of soil including sharpening driving point, protection to top end including hire charges for staging and all equipments. NB:- Payment to be made for the length actually driven below ground. (i) Where boats are not necessary. (a) 17.50 cm to 20 cm Av. Diameter	285.50	Mtr	₹ 82.40	Rupees six and paise three zero only	₹ 23,525.00
7	Supplying and fitting fixing with Iron nails, half split Eucalyptus Bullah walling pieces and cross pieces with the thicker end as specified below with cost of all materials and carriage to site etc. complete. (a) Above 15.00 cm.	167.00	Mtr	₹ 93.90	Rupees nine and paise two zero only	₹ 15,681.00



Sl. No.	Description of Items	No. or Quantity	Unit	Estimated Rate		Amount
				Figure	Word	
8	Coal tarring with 5% pitch including cost of all materials complete. (b) Two coats.	288.98	Sqm	₹ 26.80	Rupees one hundred thirty eight and paise nine zero only	₹ 7,745.00
9	Fitting, fixing bitumen drum sheet to bullah piling and wailing pieces including cutting straightening drum sheet fixing with country nails and bolts including supply of drum sheet fixture all complete as per direction of the Engineer - in - Charge.	11.20	Sqm	₹ 305.90	Rupees sixty two and paise one zero only	₹ 3,426.00
10	Earthwork, transporting the earth by manually operated thela/ van/ ricksaw etc. beyond the lead of 150 metres and upto 500 metre including removal of jungle and trees upto 30 cm girth, all cost of excavation of earth in all kinds of soil, loading, transporting, unloading, stacking, placing the same or making embankments, rough dressing etc. including all lifts, as directed by the Engineer-in-charge.	111.00	Cum	₹ 138.90	Rupees one hundred thirty eight and paise nine zero only	₹ 15,418.00
11	Extra rate in item no. 1.08 above for each additional lead of 500 metre or part there of beyond the initial lead of 500 metre. NB:- This item is applicable only where the track/ tractors are not accessible at site. 9 (nine) Extra Lead	111.00	Cum	₹ 186.30	Rupees one hundred thirty one and paise seven zero only	₹ 20,679.00
12	Carriage of boulder upto 5.0 Km by tractor/trolley or by any other conveyance including loading and unloading where the trucks are not accessible to site N.B.- This item can only be used after obtaining approval of route chart from Superintending Engineer	574.00	Cum	₹ 186.30	Rupees one hundred thirty one and paise seven zero only	₹ 1,06,936.00
Total Amount put to Tender in figure =						₹ 4,66,467.00
Total Amount put to Tender in word :						Rupees four lakh sixty six thousand four hundred sixty seven only

  
Executive Engineer  
West Midnapore Division  
Irrigation & Waterways Dte.  
Paschim Medinipur

I / We do hereby agree to do the above work @.....

Above / Less / At par than this Schedule Of Rates attached herewith.

\_\_\_\_\_  
(Signature of the Contractor)